# Illustrated Parts Manual

## *Models*
## *600S*
## *660SJ*

**PVC**
**2001**
**2007**

**P/N**
**31215035**

**May 15, 2020 - Rev B**

***ANSI***

***CE***

***AS/NZS***

An Oshkosh Corporation Company

MidWestTech | JLG 600S, 660SJ Boom Lift Parts Manual | Publication 31215035

Order the manual at mid-west-tech.com >

# TABLE OF CONTENTS


SECTION 1 - FRAME ..... 15

FIGURE 1-1. AXLE INSTALLATION - FRONT ..... 16
FIGURE 1-2. AXLE INSTALLATION - REAR (4WS ONLY) ..... 18
FIGURE 1-3. STEER INSTALLATION - WITHOUT TOW PACKAGE ..... 20
FIGURE 1-4. STEER INSTALLATION - WITH TOW PACKAGE ..... 22
FIGURE 1-5. WHEEL DRIVE INSTALLATION - 4WD/2WS ..... 24
FIGURE 1-6. WHEEL DRIVE INSTALLATION - 4WD/4WS ..... 26
FIGURE 1-7. DRIVE MOTOR ASSEMBLY ..... 28
FIGURE 1-8. DRIVE HUB ASSEMBLY ..... 30
FIGURE 1-9. TRACTION VALVE ASSEMBLY (PVC 2001) ..... 34
FIGURE 1-10. TRACTION VALVE ASSEMBLY (PVC 2007) ..... 36
FIGURE 1-11. TIRE & WHEEL INSTALLATION - IN355-55 D625 FOAM FILLED (AVAILABLE ON ALL SPECS) ..... 38
FIGURE 1-12. TIRE & WHEEL INSTALLATION - IN355-55 D625 FOAM FILLED NON-MARKING (AVAILABLE ON ALL SPECS) ..... 40
FIGURE 1-13. TIRE & WHEEL INSTALLATION - 41-18LL X 22.5 FOAM FILLED TURF & SAND (AVAILABLE ON ALL SPECS EXCEPT AUSTRALIAN & CE SPECS) ..... 42
FIGURE 1-14. LP TANKS AND BRACKETS INSTALLATION (FORD ENGINES) ..... 44
FIGURE 1-15. FRAME COVERS INSTALLATION - 2WS ..... 46
FIGURE 1-16. FRAME COVERS INSTALLATION - 4WS ..... 48
FIGURE 1-17. TOW BAR INSTALLATION ..... 50

SECTION 2 - TURNTABLE ..... 53

FIGURE 2-1. VALVE INSTALLATION - 600S WITH 2WS ..... 54
FIGURE 2-2. VALVE INSTALLATION - 600S WITH 4WS ..... 56
FIGURE 2-3. VALVE INSTALLATION - 660SJ WITH 2WS ..... 58
FIGURE 2-4. VALVE INSTALLATION - 660SJ WITH 4WS ..... 60
FIGURE 2-5. MAIN VALVE ASSEMBLY - 2WS ..... 62
FIGURE 2-6. MAIN VALVE ASSEMBLY - 4WS ..... 66
FIGURE 2-7. AXLE VALVE ASSEMBLY ..... 70
FIGURE 2-8. SWING DRIVE INSTALLATION ..... 72
FIGURE 2-9. SWING MOTOR/HUB ASSEMBLY ..... 74
FIGURE 2-10. TURNTABLE BEARING AND LUBE INSTALLATION ..... 78
FIGURE 2-11. TURNTABLE LOCK INSTALLATION ..... 80
FIGURE 2-12. ROTARY COUPLING INSTALLATION - 2WS ..... 82
FIGURE 2-13. ROTARY COUPLING ASSEMBLY - 2WS ..... 84
FIGURE 2-14. ROTARY COUPLING INSTALLATION - 4WS ..... 86
FIGURE 2-15. TANKS INSTALLATION - DIESEL MACHINES (POLY FUEL TANK) ..... 88
FIGURE 2-16. TANKS INSTALLATION - DIESEL MACHINES (STEEL FUEL TANK) ..... 90
FIGURE 2-17. TANKS INSTALLATION - GAS MACHINES ..... 92
FIGURE 2-18. HYDRAULIC TANK ASSEMBLY ..... 94
FIGURE 2-19. BATTERY AND AUXILIARY PUMP INSTALLATION ..... 96
FIGURE 2-20. BATTERY AND AUXILIARY PUMP WITH DISCONNECT SWITCH INSTALLATION ..... 98
FIGURE 2-21. ELECTRICAL COMPONENTS INSTALLATION- 600S WITH 2WS ..... 100
FIGURE 2-22. ELECTRICAL COMPONENTS INSTALLATION - 600S WITH 2WS AND DEUTZ TD2.2L3 (STAGE V) ENGINE (PVC 2007) ..... 102
FIGURE 2-23. ELECTRICAL COMPONENTS INSTALLATION - 600S WITH 4WS ..... 104
FIGURE 2-24. ELECTRICAL COMPONENTS INSTALLATION - 600S WITH 4WS AND DEUTZ TD2.2L3 (STAGE V) ENGINE (PVC 2007) ..... 106
FIGURE 2-25. ELECTRICAL COMPONENTS INSTALLATION - 660SJ WITH 2WS ..... 108
FIGURE 2-26. ELECTRICAL COMPONENTS INSTALLATION - 660SJ WITH 2WS AND DEUTZ TD2.2L3 (STAGE V) ENGINE (PVC 2007) ..... 110
FIGURE 2-27. ELECTRICAL COMPONENTS INSTALLATION - 660SJ WITH 4WS ..... 112
FIGURE 2-28. ELECTRICAL COMPONENTS INSTALLATION - 660SJ WITH 4WS AND DEUTZ TD2.2L3 (STAGE V) ENGINE (PVC 2007) ..... 114
FIGURE 2-29. GROUND CONTROL ASSEMBLY - 600S ..... 116
FIGURE 2-30. GROUND CONTROL ASSEMBLY - 600S WITH DEUTZ TD2.2L3 (STAGE V) ENGINE ..... 118
FIGURE 2-31. GROUND CONTROL ASSEMBLY - 660SJ ..... 120
FIGURE 2-32. GROUND CONTROL ASSEMBLY - 660SJ WITH DEUTZ TD2.2L3 (STAGE V) ENGINE ..... 122
FIGURE 2-33. LIGHT PANEL INSTALLATION (USA BUILT MACHINES) ..... 124
FIGURE 2-34. LIGHT PANEL INSTALLATION (CHINA BUILT MACHINES) ..... 126
FIGURE 2-35. KEYSWITCH INSTALLATION - 600S (ANSI, ANSI EXPORT, CSA AND JAPANESE SPECS) ..... 128
FIGURE 2-36. KEYSWITCH INSTALLATION - 600S (CE SPECS) (PVC 2001) ..... 130
FIGURE 2-37. KEYSWITCH INSTALLATION - 600S WITH DEUTZ TD2.2L3 (STAGE V) ENGINE (CE SPECS) (PVC 2007) ..... 132
FIGURE 2-38. KEYSWITCH INSTALLATION - 660SJ (ALL SPECS EXCEPT CE SPECS) ..... 134





MidWestTech | JLG 600S, 660SJ Boom Lift Parts Manual | Publication 31215035 Order the manual at mid-west-tech.com >

# TABLE OF CONTENTS


FIGURE 2-39. KEYSWITCH INSTALLATION - 660SJ (CE SPECS) (PVC 2001) ..... 136
FIGURE 2-40. KEYSWITCH INSTALLATION - 660SJ WITH DEUTZ TD2.2L3 (STAGE V) ENGINE (CE SPECS) (PVC 2007) ..... 138
FIGURE 2-41. STROBE LIGHT INSTALLATION - AMBER (OPTIONAL) ..... 140
FIGURE 2-42. STROBE LIGHT INSTALLATION - BLUE (OPTIONAL) ..... 142
FIGURE 2-43. STROBE LIGHT INSTALLATION - RED (OPTIONAL) ..... 144
FIGURE 2-44. WHITE NOISE ALARM INSTALLATION ..... 146
FIGURE 2-45. HOODS INSTALLATIONS - ABS (DEUTZ D2.9L4 - 49HP ENGINE) ..... 148
FIGURE 2-46. HOODS INSTALLATIONS - ABS (DEUTZ D2011, DEUTZ TD2.9L4 - 67HP AND FORD ENGINES) ..... 152
FIGURE 2-47. HOOD ASSEMBLY - ENGINE SIDE (ABS) ..... 156
FIGURE 2-48. HOOD ASSEMBLY - TANK SIDE (ABS) ..... 158
FIGURE 2-49. HOODS INSTALLATIONS - STEEL (USA BUILT MACHINES) (DEUTZ D2.9L4 – 49HP ENGINE) ..... 160
FIGURE 2-50. HOODS INSTALLATIONS - STEEL (USA BUILT MACHINES) (DEUTZ D2011, DEUTZ TD2.9L4 – 67HP AND FORD ENGINES) ..... 164
FIGURE 2-51. HOODS INSTALLATIONS - STEEL (CHINA BUILT MACHINES) ..... 168
FIGURE 2-52. HOOD ASSEMBLY - ENGINE SIDE (STEEL) (USA BUILT MACHINES) ..... 172
FIGURE 2-53. HOOD ASSEMBLY - ENGINE SIDE (STEEL) (CHINA BUILT MACHINES) ..... 174
FIGURE 2-54. HOOD ASSEMBLY - TANK SIDE (STEEL) (USA BUILT MACHINES) ..... 176
FIGURE 2-55. HOOD ASSEMBLY - TANK SIDE (STEEL) (CHINA BUILT MACHINES) ..... 178
FIGURE 2-56. NOISE REDUCTION PACKAGE - 600S ..... 180
FIGURE 2-57. NOISE REDUCTION PACKAGE - 660SJ ..... 182
FIGURE 2-58. TURNTABLE COVERS INSTALLATION ..... 184

SECTION 3 - ENGINE ..... 187

FIGURE 3-1. DEUTZ D2011 ENGINE INSTALLATION - WITHOUT ARCTIC PACKAGE ..... 188
FIGURE 3-2. DEUTZ D2011 ENGINE AND PUMPS SUB-ASSEMBLY - WITHOUT ARCTIC PACKAGE ..... 190
FIGURE 3-3. DEUTZ D2011 ENGINE ASSEMBLY - WITHOUT ARCTIC PACKAGE ..... 192
FIGURE 3-4. DEUTZ D2011 ENGINE INSTALLATION - WITH ARCTIC PACKAGE ..... 196
FIGURE 3-5. DEUTZ D2011 ENGINE AND PUMPS SUB-ASSEMBLY - WITH ARCTIC PACKAGE ..... 200
FIGURE 3-6. DEUTZ D2011 ENGINE ASSEMBLY - WITH ARCTIC PACKAGE ..... 202
FIGURE 3-7. DEUTZ D2011 ENGINE COMPONENTS ..... 206
FIGURE 3-8. DEUTZ D2011 (STAGE V) ENGINE INSTALLATION (PVC 2001) ..... 210
FIGURE 3-9. DEUTZ D2011 (STAGE V) ENGINE AND PUMPS SUB-ASSEMBLY (PVC 2001) ..... 212
FIGURE 3-10. DEUTZ D2011 (STAGE V) ENGINE ASSEMBLY (PVC 2001) ..... 214
FIGURE 3-11. DEUTZ D2011 (STAGE V) ENGINE COMPONENTS (PVC 2001) ..... 218
FIGURE 3-12. DEUTZ TD2.2L3 (STAGE V) ENGINE INSTALLATION (PVC 2007) ..... 222
FIGURE 3-13. DEUTZ TD2.2L3 (STAGE V) ENGINE AND PUMPS SUB-ASSEMBLY (PVC 2007) ..... 226
FIGURE 3-14. DEUTZ TD2.2L3 (STAGE V) ENGINE ASSEMBLY (PVC 2007) ..... 228
FIGURE 3-15. DEUTZ D2.9L4 - 49HP ENGINE INSTALLATION - WITHOUT ARCTIC PACKAGE ..... 232
FIGURE 3-16. DEUTZ D2.9L4 - 49HP ENGINE AND PUMPS SUB-ASSEMBLY - WITHOUT ARCTIC PACKAGE ..... 236
FIGURE 3-17. DEUTZ D2.9L4 - 49HP ENGINE ASSEMBLY - WITHOUT ARCTIC PACKAGE (PVC 2001) ..... 238
FIGURE 3-18. DEUTZ D2.9L4 - 49HP ENGINE ASSEMBLY - WITHOUT ARCTIC PACKAGE (PVC 2007) ..... 242
FIGURE 3-19. DEUTZ D2.9L4 - 49HP ENGINE INSTALLATION - WITH ARCTIC PACKAGE ..... 248
FIGURE 3-20. DEUTZ D2.9L4 - 49HP ENGINE AND PUMPS SUB-ASSEMBLY - WITH ARCTIC PACKAGE ..... 252
FIGURE 3-21. DEUTZ D2.9L4 - 49HP ENGINE ASSEMBLY - WITH ARCTIC PACKAGE (PVC 2001) ..... 254
FIGURE 3-22. DEUTZ D2.9L4 - 49HP ENGINE ASSEMBLY - WITH ARCTIC PACKAGE (PVC 2007) ..... 258
FIGURE 3-23. DEUTZ D2.9L4 - 49HP ENGINE COMPONENTS ..... 264
FIGURE 3-24. DEUTZ TD2.9L4 - 67HP ENGINE INSTALLATION - WITHOUT ARCTIC PACKAGE ..... 266
FIGURE 3-25. DEUTZ TD2.9L4 - 67HP ENGINE AND PUMPS SUB-ASSEMBLY - WITHOUT ARCTIC PACKAGE ..... 270
FIGURE 3-26. DEUTZ TD2.9L4 - 67HP ENGINE ASSEMBLY - WITHOUT ARCTIC PACKAGE (PVC 2001) ..... 272
FIGURE 3-27. DEUTZ TD2.9L4 - 67HP ENGINE ASSEMBLY - WITHOUT ARCTIC PACKAGE (PVC 2007) ..... 276
FIGURE 3-28. DEUTZ TD2.9L4 - 67HP ENGINE INSTALLATION - WITH ARCTIC PACKAGE ..... 280
FIGURE 3-29. DEUTZ TD2.9L4 - 67HP ENGINE AND PUMPS SUB-ASSEMBLY - WITH ARCTIC PACKAGE ..... 284
FIGURE 3-30. DEUTZ TD2.9L4 - 67HP ENGINE ASSEMBLY - WITH ARCTIC PACKAGE (PVC 2001) ..... 286
FIGURE 3-31. DEUTZ TD2.9L4 - 67HP ENGINE ASSEMBLY - WITH ARCTIC PACKAGE (PVC 2007) ..... 290
FIGURE 3-32. DEUTZ TD2.9L4 - 67HP ENGINE COMPONENTS ..... 294
FIGURE 3-33. BREATHER HEATER INSTALLATION - DEUTZ D2.9L4 - 49HP AND DEUTZ TD2.9L4 - 67HP ENGINES WITH ARCTIC PACKAGE ..... 300
FIGURE 3-34. FORD ENGINE INSTALLATION - WITHOUT ARCTIC PACKAGE ..... 302
FIGURE 3-35. FORD ENGINE AND PUMPS SUB-ASSEMBLY - WITHOUT ARCTIC PACKAGE ..... 306
FIGURE 3-36. FORD ENGINE ASSEMBLY - WITHOUT ARCTIC PACKAGE ..... 308
FIGURE 3-37. FORD ENGINE INSTALLATION - WITH ARCTIC PACKAGE ..... 314
FIGURE 3-38. FORD ENGINE AND PUMPS SUB-ASSEMBLY - WITH ARCTIC PACKAGE ..... 318
FIGURE 3-39. FORD ENGINE ASSEMBLY - WITH ARCTIC PACKAGE ..... 320
FIGURE 3-40. FORD ENGINE PREP ASSEMBLY ..... 326
FIGURE 3-41. FORD ENGINE COMPONENTS ..... 328
FIGURE 3-42. PUMP COUPLING KIT (DEUTZ ENGINES) ..... 332





MidWestTech | JLG 600S, 660SJ Boom Lift Parts Manual | Publication 31215035 Order the manual at mid-west-tech.com >

FIGURE 3-43. PISTON PUMP ASSEMBLY ..... 334
FIGURE 3-44. FUEL FILTER INSTALLATION (POLY FUEL TANK) ..... 338
FIGURE 3-45. FUEL FILTER INSTALLATION (STEEL FUEL TANK) (DEUTZ D2011 ENGINES) ..... 340
FIGURE 3-46. FUEL FILTER INSTALLATION (STEEL FUEL TANK) (DEUTZ TD2.9L4 ENGINES) ..... 342
FIGURE 3-47. MUFFLER INSTALLATION - SPARK ARRESTING (DEUTZ D2011 ENGINES) ..... 344
FIGURE 3-48. EXHAUST PIPE INSTALLATION - (DEUTZ D2011 ENGINES) ..... 346
FIGURE 3-49. MOTOR MOUNT INSTALLATION - WITHOUT GENERATOR (DEUTZ D2011 ENGINES) ..... 348
FIGURE 3-50. MOTOR MOUNT INSTALLATION - WITHOUT GENERATOR (DEUTZ TD2.2L3 (STAGE V) ENGINES) (PVC 2007) ..... 350
FIGURE 3-51. MOTOR MOUNT INSTALLATION - WITHOUT GENERATOR (DEUTZ TD2.9L4 - 49HP ENGINES) ..... 352
FIGURE 3-52. MOTOR MOUNT INSTALLATION - WITHOUT GENERATOR (DEUTZ TD2.9L4 - 67HP ENGINES) ..... 354
FIGURE 3-53. MOTOR MOUNT INSTALLATION - WITH GENERATOR (DEUTZ D2011 ENGINES) ..... 356
FIGURE 3-54. MOTOR MOUNT INSTALLATION - WITH GENERATOR (DEUTZ TD2.2L3 (STAGE V) ENGINES) (PVC 2007) 358
FIGURE 3-55. MOTOR MOUNT INSTALLATION - WITH GENERATOR (DEUTZ TD2.9L4 - 49HP ENGINES) ..... 360
FIGURE 3-56. MOTOR MOUNT INSTALLATION - WITH GENERATOR (DEUTZ TD2.9L4 - 67HP ENGINES) ..... 362
FIGURE 3-57. BELT WITHOUT GENERATOR INSTALLATION (FORD ENGINES) ..... 364
FIGURE 3-58. TRAY JACK INSTALLATION (DEUTZ D2011, DEUTZ TD2.9L4 - 67HP AND FORD ENGINES) ..... 366
FIGURE 3-59. TRAY JACK INSTALLATION (DEUTZ TD2.2L3 (STAGE V) ENGINE AND DEUTZ D2.9L4 - 49HP ENGINES) . 368
FIGURE 3-60. ENGINE HOOD BAFFLES INSTALLATION - ABS HOODS (DEUTZ D2011, DEUTZ TD2.9L4 - 67HP AND FORD ENGINES) ..... 370
FIGURE 3-61. ENGINE HOOD BAFFLES INSTALLATION - ABS HOODS (DEUTZ D2.9L4 - 49HP ENGINES) ..... 372
FIGURE 3-62. ENGINE HOOD BAFFLES INSTALLATION - STEEL HOODS (DEUTZ D2011, DEUTZ TD2.9L4 - 67HP AND FORD ENGINES) ..... 374
FIGURE 3-63. ENGINE HOOD BAFFLES INSTALLATION - STEEL HOODS (DEUTZ D2.9L4 - 49HP ENGINES) ..... 376
FIGURE 3-64. 2500W GENERATOR INSTALLATION - 110V/60HZ (DEUTZ D2011 ENGINES) (OPTIONAL) ..... 378
FIGURE 3-65. 2500W GENERATOR INSTALLATION - 110V/60HZ (DEUTZ D2.9L4 - 49HP ENGINES) (OPTIONAL) ..... 380
FIGURE 3-66. 2500W GENERATOR INSTALLATION - 110V/60HZ (DEUTZ TD2.9L4 - 67HP ENGINES) (OPTIONAL) ..... 384
FIGURE 3-67. 2500W GENERATOR INSTALLATION - 110V/60HZ (FORD ENGINES) (OPTIONAL) ..... 388
FIGURE 3-68. 2500W GENERATOR INSTALLATION - 220V/50HZ (DEUTZ D2011 ENGINES) (OPTIONAL) ..... 390
FIGURE 3-69. 4000W GENERATOR INSTALLATION - 110V/60HZ (DEUTZ D2011 ENGINES) (OPTIONAL) ..... 392
FIGURE 3-70. 4000W GENERATOR INSTALLATION - 110V/60HZ (DEUTZ D2.9L4 - 49HP ENGINES) (OPTIONAL) ..... 396
FIGURE 3-71. 4000W GENERATOR INSTALLATION - 110V/60HZ (DEUTZ TD2.9L4 - 67HP ENGINES) (OPTIONAL) ..... 400
FIGURE 3-72. 4000W GENERATOR INSTALLATION - 220V/50HZ (DEUTZ D2011 ENGINES) (OPTIONAL) ..... 404
FIGURE 3-73. 4000W GENERATOR INSTALLATION - 220V/50HZ (DEUTZ TD2.2L3 (STAGE V) ENGINE) (OPTIONAL) (PVC 2007) ..... 408
FIGURE 3-74. 4000W GENERATOR INSTALLATION - 220V/50HZ (DEUTZ TD2.9L4 - 67HP ENGINES) (OPTIONAL) ..... 410
FIGURE 3-75. 7500W SKYPOWER GENERATOR INSTALLATION - 110/60HZ (DEUTZ D2011 ENGINES) (OPTIONAL) ..... 414
FIGURE 3-76. 7500W SKYPOWER GENERATOR INSTALLATION - 110V/60HZ (DEUTZ D2.9L4 - 49HP ENGINES) (OPTIONAL) ..... 418
FIGURE 3-77. 7500W SKYPOWER GENERATOR INSTALLATION - 110V/60HZ (DEUTZ TD2.9L4 - 67HP ENGINES) (OPTIONAL) ..... 422
FIGURE 3-78. 7500W SKYPOWER GENERATOR INSTALLATION - 110V/60HZ (FORD ENGINES) (OPTIONAL) ..... 426
FIGURE 3-79. 7500W SKYPOWER GENERATOR INSTALLATION - 220V/50HZ (DEUTZ D2011 ENGINES) (OPTIONAL) ..... 430
FIGURE 3-80. 7500W SKYPOWER GENERATOR INSTALLATION - 220V/50HZ (DEUTZ TD2.2L3 (STAGE V) ENGINE) (OPTIONAL) (PVC 2007) ..... 434
FIGURE 3-81. 7500W SKYPOWER GENERATOR INSTALLATION - 220V/50HZ (DEUTZ TD2.9L4 - 67HP ENGINES) (OPTIONAL) ..... 438

SECTION 4 - BOOM ..... 441

FIGURE 4-1. BOOM INSTALLATION - 600S ..... 442
FIGURE 4-2. BOOM INSTALLATION - 660SJ ..... 446
FIGURE 4-3. BOOM ASSEMBLY - 600S ..... 450
FIGURE 4-4. BOOM ASSEMBLY - 660SJ ..... 454
FIGURE 4-5. JIB ASSEMBLY - 660SJ (USA BUILT MACHINES) ..... 458
FIGURE 4-6. JIB ASSEMBLY - 660SJ (CHINA BUILT MACHINES) ..... 460
FIGURE 4-7. PLATFORM ROTATOR ASSEMBLY - 600S ..... 462
FIGURE 4-8. PLATFORM ROTATOR ASSEMBLY - 660SJ ..... 464
FIGURE 4-9. POWER TRACK INSTALLATION (PVC 2001) ..... 466
FIGURE 4-10. POWER TRACK INSTALLATION (PVC 2007) ..... 468
FIGURE 4-11. BOOM VALVES INSTALLATION - 600S WITH 2WS ..... 470
FIGURE 4-12. BOOM VALVES INSTALLATION - 600S WITH 4WS ..... 472
FIGURE 4-13. BOOM VALVES INSTALLATION - 660SJ WITH 2WS ..... 474
FIGURE 4-14. BOOM VALVES INSTALLATION - 660SJ WITH 4WS ..... 476
FIGURE 4-15. PLATFORM VALVE ASSEMBLY - 600S ..... 478
FIGURE 4-16. PLATFORM VALVE ASSEMBLY - 660SJ ..... 480
FIGURE 4-17. BOOM SENSORS INSTALLATION - 600S (USA BUILT MACHINES) ..... 482



MidWestTech | JLG 600S, 660SJ Boom Lift Parts Manual | Publication 31215035 Order the manual at mid-west-tech.com >

## FIGURE 5-5. PLATFORM ASSEMBLY - 30IN X 5FT (76CM X 1.52M) WITH DROP BAR

| ITEM | PART NUMBER | QTY | DESCRIPTION | REV |
|---|---|---|---|---|
| | 1001186377 | Ref | PLATFORM ASSEMBLY | C |
| | | Ref | Note: Platform and Mesh must be ordered separately for Platforms with Mesh. See SPECIAL OPTIONS SECTION for Mesh Installations. | |
| | | Ref | Note: Replacement Decals Must be Ordered Separately - See DECALS SECTION. | |
| 1 | 0100011 | AR | Compound, Locking | |
| 2 | 0641420 | 2 | Bolt 1/4 x 2-1/2 | |
| 3 | 0961845 | 2 | Bushing | |
| 4 | 3290606 | 2 | Nut M6 | |
| 5 | 3300151 | 2 | Nut 1/4 | |
| 6 | 3520072 | 2 | Plug | |
| 7 | 3520198 | 2 | Plug | |
| 8 | 4010618 | 2 | Screw M6 x 50 | |
| 9 | 4711400 | 4 | Washer 1/4 | |
| 10 | 4811700 | 2 | Washer M6 | |
| 11 | 1001138494 | 1 | Bar, Drop | |
| 12 | 1001138514 | 1 | Rail (Top) | |
| 13 | 1001140429 | 1 | Decal - Drop Bar | |
| 14 | See Note | NSS | Platform (Note: Not Available - Purchase Platform Assembly) | |



MidWestTech | JLG 600S, 660SJ Boom Lift Parts Manual | Publication 31215035 Order the manual at mid-west-tech.com >

## FIGURE 5-31. SKYGLAZIER INSTALLATION - 600S (BRAZIL SPECS)

| ITEM | PART NUMBER | QTY | DESCRIPTION | REV |
|---|---|---|---|---|
| | 1001229022 | Ref | SKYGLAZIER INSTALLATION | A |
| 1 | 0642012 | 2 | Bolt 5/8 x 1-1/2 | |
| 2 | 0642212 | 4 | Bolt 3/4 x 1-1/2 | |
| 3 | 2902212 | 1 | Bumpers and Strap Kit | |
| 3 | 0940102 | 1 | Bumper Only | |
| 3 | 4240149 | 1 | Strap Only | |
| 4 | 3312005 | 4 | Nut 5/8 | |
| 5 | 3312205 | 4 | Nut 3/4 | |
| 6 | 4420014 | AR | Tape | |
| 7 | 4712000 | 6 | Washer 5/8 | |
| 8 | 4712200 | 8 | Washer 3/4 | |
| 9 | 8310129 | 2 | Bolt 3/4 x 2-1/2 | |
| 10 | 1001099366 | 1 | Support | |
| 11 | 1001099367 | 1 | Support | |
| 12 | 1001229118 | 1 | Tray Assembly (See Items 101-111 for Breakdown) | |
| | 1001229118 | Ref | TRAY ASSEMBLY | B |
| 101 | 0100081 | AR | Adhesive | |
| 102 | 1120555 | 2 | Cap, Tube | |
| 103 | 1701509 | 1 | Decal - Manual | |
| 104 | See Note | NSS | Nameplate - Serial Number (Note: Not Available for Purchase) | |
| 106 | 3340956 | 1 | Pad Kit | |
| 107 | 3460334 | 1 | Tube | |
| 108 | 3520071 | 2 | Plug | |
| 109 | 4420066 | AR | Tape, Double Sided | |
| 111 | 1001229112 | 2 | Decal - Glazier Capacity | |
| | 0272418 | Ref | SKYGLAZIER DECAL INSTALLATION | 4 |
| 201 | 1705358 | 2 | Decal - SkyGlazier | |



MidWestTech | JLG 600S, 660SJ Boom Lift Parts Manual | Publication 31215035 Order the manual at mid-west-tech.com >

## FIGURE 6-3. LEVEL CYLINDER ASSEMBLY - PLATFORM SLAVE (660SJ)

| ITEM | PART NUMBER | QTY | DESCRIPTION | REV |
|---|---|---|---|---|
| | 1001184957 | Ref | LEVEL CYLINDER ASSEMBLY | D |
| 1 | 70005698 | 1 | Barrel | |
| 2 | 70005699 | 1 | Rod | |
| 3 | 70005700 | 1 | Head | |
| 4 | See Note | NSS | Wiper (Note: Use Item 100) | |
| 5 | 70002410 | 1 | Ring, Retaining | |
| 6 | See Note | NSS | Seal, Rod (Note: Use Item 100) | |
| 7 | See Note | NSS | Ring, Back-up (Note: Use Item 100) | |
| 8 | 70004237 | 1 | Bearing | |
| 9 | See Note | NSS | O-Ring (Note: Use Item 100) | |
| 10 | See Note | NSS | Ring, Back-up (Note: Use Item 100) | |
| 11 | See Note | NSS | O-Ring (Note: Use Item 100) | |
| 12 | 70005701 | 1 | Piston | |
| 13 | See Note | NSS | Seal, Piston (Note: Use Item 100) | |
| 14 | See Note | NSS | O-Ring (Note: Use Item 100) | |
| 15 | 70022564 | 1 | Ball | |
| 16 | 70023369 | 1 | Setscrew | |
| 17 | 0961948 | 4 | Bearing | |
| 18 | 2220883 | 10 | Plug | |
| 19 | 70005702 | 1 | Spacer | |
| 20 | 4640999 | 1 | Valve, Counterbalance | |
| 20 | 2900792 | 1 | Seal Kit - 4640999 Valve | |
| 21 | 4640932 | 1 | Valve, Counterbalance | |
| 21 | 7011112 | 1 | Seal Kit - 4640932 Valve | |
| 100 | 70005703 | 1 | Seal Kit - 1001184957 Cylinder (Include Items 4, 6, 7, 9, 10, 11, 13 & 14) | |



MidWestTech | JLG 600S, 660SJ Boom Lift Parts Manual | Publication 31215035 Order the manual at mid-west-tech.com >