Illustrated Parts Manual

Model

R3246

PVC
1910
2004

P/N
31215093

March 15, 2020 - Rev B

ANSI

AS/NZS

An Oshkosh Corporation Company

MidWestTech | JLG R3246 Scissor Lift Parts Manual | Publication 31215093

Order the manual at mid-west-tech.com >

TABLE OF CONTENTS

SECTION 1 - FRAME 11

FIGURE 1-1. STEER INSTALLATION 12
FIGURE 1-2. DRIVE/BRAKE INSTALLATION 14
FIGURE 1-3. DRIVE MOTOR ASSEMBLY 16
FIGURE 1-4. TIRE/WHEEL INSTALLATION 18
FIGURE 1-5. POTHOLE PROTECTION SYSTEM INSTALLATION 20
FIGURE 1-6. TILT SENSOR INSTALLATION 22
FIGURE 1-7. BATTERY CHARGER INSTALLATION - DELTA-Q WITHOUT COMMUNICATION PORT (LOCALLY SUPPLIED PLUG) 24
FIGURE 1-8. BATTERY CHARGER INSTALLATION - DELTA-Q WITH COMMUNICATION PORT (LOCALLY SUPPLIED PLUG) 26
FIGURE 1-9. BATTERY CHARGER INSTALLATION - DELTA-Q WITHOUT COMMUNICATION PORT (110V PLUG) 28
FIGURE 1-10. BATTERY CHARGER INSTALLATION - DELTA-Q WITH COMMUNICATION PORT (110V PLUG) 30
FIGURE 1-11. BATTERY CHARGER INSTALLATION - DELTA-Q WITHOUT COMMUNICATION PORT (AUSTRALIAN PLUG) 32
FIGURE 1-12. BATTERY CHARGER INSTALLATION - DELTA-Q WITH COMMUNICATION PORT (AUSTRALIAN PLUG) 34
FIGURE 1-13. BATTERY CHARGER INSTALLATION - DELTA-Q WITHOUT COMMUNICATION PORT (KOREAN PLUG) 36
FIGURE 1-14. BATTERY CHARGER INSTALLATION - DELTA-Q WITH COMMUNICATION PORT (KOREAN PLUG) 38
FIGURE 1-15. BATTERY CHARGER INSTALLATION - EAGLE PERFORMANCE (110V PLUG) 40
FIGURE 1-16. BATTERY CHARGER INSTALLATION - GREEN POWER (LOCALLY SUPPLIED PLUG) 42
FIGURE 1-17. BATTERY CHARGER INSTALLATION - GREEN POWER (CHINA PLUG) 44
FIGURE 1-18. STROBE LIGHT INSTALLATION - SINGLE (AMBER) (WITHOUT GUARD) 46
FIGURE 1-19. STROBE LIGHT INSTALLATION - DUAL (AMBER) (WITHOUT GUARD) 48
FIGURE 1-20. STROBE LIGHT INSTALLATION - SINGLE (AMBER) (WITH GUARD) 50
FIGURE 1-21. STROBE LIGHT INSTALLATION - DUAL (AMBER) (WITH GUARD) 52
FIGURE 1-22. ALARM INSTALLATION (AMBIENT/WHITE NOISE) 54
FIGURE 1-23. LADDER INSTALLATION 56
FIGURE 1-24. FRAME COVERS INSTALLATION 58

SECTION 2 - GROUND CONTROLS 61

FIGURE 2-1. HYDRAULIC COMPONENTS INSTALLATION 62
FIGURE 2-2. MAIN VALVE ASSEMBLY 64
FIGURE 2-3. ELECTRICAL COMPONENTS INSTALLATION (CHINA & MEXICO BUILT MACHINES) 66
FIGURE 2-4. ELECTRICAL COMPONENTS INSTALLATION - #1 (EUROPEAN BUILT MACHINES) 68
FIGURE 2-5. ELECTRICAL COMPONENTS INSTALLATION - #2 (EUROPEAN BUILT MACHINES) 70
FIGURE 2-6. ACCESS CONTROL KEYPAD INSTALLATION 72
FIGURE 2-7. MOBILE CONTROL INSTALLATION 74
FIGURE 2-8. MDI INSTALLATION 76
FIGURE 2-9. BATTERIES INSTALLATION - STANDARD 6V-255AH 78
FIGURE 2-10. BATTERIES INSTALLATION - STANDARD 6V-220AH 80
FIGURE 2-11. BATTERIES INSTALLATION - AGM 6V-220AH 82
FIGURE 2-12. BATTERIES INSTALLATION - AGM EVCG 6V-220AH 84
FIGURE 2-13. BATTERIES INSTALLATION - 6V-220AH (TROJAN) 86
FIGURE 2-14. INVERTER INSTALLATION (OPTIONAL) 88
FIGURE 2-15. DOORS INSTALLATION 90

SECTION 3 - SCISSORS ARMS 93

FIGURE 3-1. SCISSORS ARMS INSTALLATION 94
FIGURE 3-2. ARMS GUARD INSTALLATION 98

SECTION 4 - PLATFORM 101

FIGURE 4-1. PLATFORM INSTALLATION 102
FIGURE 4-2. PLATFORM EXTENSION INSTALLATION 104
FIGURE 4-3. RAILS INSTALLATION (SIDE BY SIDE) 106
FIGURE 4-4. RAILS INSTALLATION (TUBE IN TUBE) 108
FIGURE 4-5. EXTENSION HANDLES INSTALLATION (OPTIONAL) 110
FIGURE 4-6. PLATFORM CONSOLE INSTALLATION (PVC1910) 112
FIGURE 4-7. PLATFORM CONSOLE INSTALLATION (PVC2004) 114
FIGURE 4-8. CONTROLLER ASSEMBLY 116
FIGURE 4-9. GATE LATCH INSTALLATION 118
FIGURE 4-10. PIPE RACKS INSTALLATION (SIDE BY SIDE RAILS) (OPTIONAL) 120
FIGURE 4-11. PIPE RACKS INSTALLATION (TUBE IN TUBE RAILS) (OPTIONAL) 122
FIGURE 4-12. OVERHEAD PROTECTION INSTALLATION (KOREAN SPECS) 124

MidWestTech | JLG R3246 Scissor Lift Parts Manual | Publication 31215093 Order the manual at mid-west-tech.com >

TABLE OF CONTENTS

SECTION 5 - CYLINDER 127

FIGURE 5-1. LIFT CYLINDER ASSEMBLY 128
FIGURE 5-2. STEER CYLINDER ASSEMBLY 130

SECTION 6 - HYDRAULIC 133

FIGURE 6-1. HYDRAULIC COMPONENTS INSTALLATION 134

SECTION 7 - ELECTRICAL 137

FIGURE 7-1. AC BOX AT PLATFORM INSTALLATION - 110V GFI (ALL SPECS EXCEPT AUSTRALIAN & CE SPECS) 138
FIGURE 7-2. AC BOX AT PLATFORM INSTALLATION - 110V IEC YELLOW (CE SPECS) 140
FIGURE 7-3. AC BOX AT PLATFORM INSTALLATION - 220V IEC BLUE (CE SPECS) 142
FIGURE 7-4. AC BOX AT PLATFORM INSTALLATION - 220V CEE7 POST GROUND (CE SPECS) 144
FIGURE 7-5. AC BOX AT PLATFORM INSTALLATION - 220V CEE7 SIDE GROUND (CE SPECS) 146
FIGURE 7-6. AC BOX AT PLATFORM INSTALLATION - 220V AFSINT 107 (CE SPECS) 148
FIGURE 7-7. AC BOX AT PLATFORM INSTALLATION - 220V CHINA PLUG (CHINA SPECS) 150
FIGURE 7-8. AC BOX AT PLATFORM INSTALLATION - 220V LOCALLY SUPPLIED COMPONENTS (ALL SPECS) 152
FIGURE 7-9. AC BOX AT PLATFORM INSTALLATION - 220V (AUSTRALIAN SPECS) 154
FIGURE 7-10. BREAKER BOX KIT WITH 1 DOUBLE BREAKER 156
FIGURE 7-11. BREAKER BOX KIT WITH 3 BREAKERS 158
FIGURE 7-12. CAN SPLICE HARNESS (CHARGER WITH COMMUNICATION PORT) 160
FIGURE 7-13. CHARGER HARNESS (CHARGER WITH COMMUNICATION PORT) (PVC 1910) 162
FIGURE 7-14. CHARGER HARNESS (CHARGER WITH COMMUNICATION PORT) (PVC 2004) 164
FIGURE 7-15. CHASSIS HARNESS 166
FIGURE 7-16. GROUND TO PLATFORM CABLE INSTALLATION - WITHOUT PLATFORM COIL CABLE (CHINA AND MEXICO BUILT MACHINES) 170
FIGURE 7-17. GROUND TO PLATFORM CABLE INSTALLATION - WITHOUT PLATFORM COIL CABLE & WITH FOOTSWITCH (CHINA BUILT MACHINES) 172
FIGURE 7-18. GROUND TO PLATFORM CABLE INSTALLATION - WITH PLATFORM COIL CABLE (CHINA AND MEXICO BUILT MACHINES) 174
FIGURE 7-19. GROUND TO PLATFORM CABLE INSTALLATION - WITH PLATFORM COIL CABLE & FOOTSWITCH (CHINA BUILT MACHINES) 176
FIGURE 7-20. GROUND TO PLATFORM CABLE INSTALLATION - PLATFORM STRAIGHT CABLE ONLY (EUROPEAN BUILT MACHINES) 178
FIGURE 7-21. GROUND TO PLATFORM CABLE INSTALLATION - PLATFORM COIL CABLE ONLY (EUROPEAN BUILT MACHINES) 180
FIGURE 7-22. GROUND TO PLATFORM CABLE INSTALLATION - SCISSORS ARMS CABLE ONLY (EUROPEAN BUILT MACHINES) 182
FIGURE 7-23. LIFT DOWN HARNESS 184
FIGURE 7-24. PLATFORM CONTROL BOX HARNESS 186
FIGURE 7-25. RECEPTACLE BOX KIT - 110V GFI 188
FIGURE 7-26. RECEPTACLE BOX KIT - 110V IEC YELLOW (CE SPEC) 190
FIGURE 7-27. RECEPTACLE BOX KIT - 220V IEC BLUE (CE SPEC) 192
FIGURE 7-28. RECEPTACLE BOX KIT - 220V CEE7 POST GROUND (CE SPEC) 194
FIGURE 7-29. RECEPTACLE BOX KIT - 220V CEE7 SIDE GROUND (CE SPEC) 196
FIGURE 7-30. RECEPTACLE BOX KIT - 220V AFSINT 107 (CE SPEC) 198

SECTION 8 - DECALS 201

FIGURE 8-1. DECAL INSTALLATION (ANSI SPECS) 202
FIGURE 8-2. DECAL INSTALLATION (AUSTRALIAN SPECS) 204
FIGURE 8-3. DECAL INSTALLATION (BRAZIL SPECS) 206
FIGURE 8-4. DECAL INSTALLATION (CE SPECS) 208
FIGURE 8-5. DECAL INSTALLATION (CHINA SPECS) 210
FIGURE 8-6. DECAL INSTALLATION (CSA SPECS) 212
FIGURE 8-7. DECAL INSTALLATION (KOREAN SPECS) 214
FIGURE 8-8. DECAL INSTALLATION (LATIN AMERICAN SPECS) 216
FIGURE 8-9. DECAL INSTALLATION - OPTIONS 218

SECTION 9 - RECOMMENDED SERVICE PARTS STOCK 219

FIGURE 9-1. RECOMMENDED SERVICE PARTS STOCK 220

SECTION 10 - SPECIAL OPTIONS 221

MidWestTech | JLG R3246 Scissor Lift Parts Manual | Publication 31215093 Order the manual at mid-west-tech.com >

FIGURE 10-1. SPECIAL OPTIONS 222

PART NUMBER INDEX 225

MidWestTech | JLG R3246 Scissor Lift Parts Manual | Publication 31215093 Order the manual at mid-west-tech.com >

FIGURE 5-1. LIFT CYLINDER ASSEMBLY

ITEM	PART NUMBER	QTY	DESCRIPTION	REV
	1001244417	Ref	LIFT CYLINDER ASSEMBLY	C
1	See Note:	NSS	Barrel (Note: Purchase Complete Part)	
2	70007050	1	Rod	
3	70007051	1	Head	
4	See Note	NSS	Wiper (Note: Use Item 50)	
5	70050795	1	Ring, Retaining	
6	See Note	NSS	Seal, Rod (Note: Use Item 50)	
7	See Note	NSS	Ring, Back-up (Note: Use Item 50)	
8	70007052	1	Bearing	
9	See Note	NSS	O-Ring (Note: Use Item 50)	
10	See Note	NSS	Ring, Back-up (Note: Use Item 50)	
11	See Note	NSS	O-Ring (Note: Use Item 50)	
12	70007053	1	Piston	
13	See Note	NSS	Seal, Piston (Note: Use Item 50)	
14	See Note	NSS	Ring, Wear (Note: Use Item 50)	
15	See Note	NSS	O-Ring (Note: Use Item 50)	
16	70007054	2	Fitting	
17	2220883	4	Plug	
18	0961948	4	Bearing	
19	70007055	1	Orifice	
20	70004585	1	Cartridge, Valve	
21	70005236	1	Cartridge, Solenoid Valve	
22	70022564	1	Ball	
23	70023369	1	Setscrew	
50	70007056	1	Seal Kit - 1001244417 Cylinder (Includes Items 4, 6, 7, 9-11 & 13-15)	

MidWestTech | JLG R3246 Scissor Lift Parts Manual | Publication 31215093 Order the manual at mid-west-tech.com >

FIGURE 8-3. DECAL INSTALLATION (BRAZIL SPECS)

ITEM	PART NUMBER	QTY	DESCRIPTION	REV
	1001238017	Ref	DECAL INSTALLATION (SPANISH/PORTUGUESE LANGUAGE)	C
	1001237749	Ref	DECAL REFERENCE CHART	E
1	2080040	3	Fastener	
2	2080057	4	Fastener	
3	8990147	1	Holder, Manual	
100	1001239270	1	Master Decal Kit	D
101	1701504	1	Decal - Hydraulic Oil	
102	1701640	1	Decal - Manual	
103	1703819	4	Decal - Direction Arrow	
104	1001248126	1	Decal – Manual Descent Instructions	
105	1704016	2	Decal - Fork Lift	
106	1704277	4	Decal - Lanyard Attach	
107	1704412	1	Decal - Hydraulic Oil	
108	1001132359	1	Decal - Control Box Locate	
109	1001162864	2	Decal - Lift Point/Tie Down	
110	1001212290	1	Decal - Tie Down	
111	1001212291	2	Decal - Lifting Lug	
112	1001237899	1	Decal - Arms Prop	
201	1702155	1	Decal - Battery Disconnect	
202	1704699	1	Decal - Danger/Warning	
203	1001146794	1	Decal - Battery/Charger Service	
204	1001216650	4	Decal - Crushing Hazard	
205	1001215748	4	Decal - Electrocution	
206	1001212292	1	Decal - No Lifting	
207	1001212293	1	Decal - No Forklift	
208	1001237538	1	Decal - Battery Spacer	
209	1704341	2	Decal - Warning Battery Ventilation	
212	1001224052	1	Decal - Yearly Inspection	
213	1001216648	4	Decal - Danger Electrocution	

MidWestTech | JLG R3246 Scissor Lift Parts Manual | Publication 31215093 Order the manual at mid-west-tech.com >

FIGURE 10-1. SPECIAL OPTIONS

ITEM	PART NUMBER	QTY	DESCRIPTION	REV
		Ref	Note: This list is to accommodate machines ordered with special equipment. Options may not be applicable to all models. For more specific parts information contact the JLG Parts Department.	
		Ref	SPECIAL OPTIONS	
	1001236903	Ref	Antivandalism Package (Factory Installed)	
	1001249639	Ref	Antivandalism Add-on Kit (Dealer Installed)	
		Ref	ClearSky Installation Options (Factory Installed):	
	1001229107	Ref	ClearSky Installation - 3-Wire (ANSI & CSA Specs)	
	1001233237	Ref	ClearSky Installation - 3-Wire (ANSI Export & CE Specs)	
	1001251146	Ref	ClearSky Installation - Canbus (ANSI, ANSI Export, Australian, CE & CSA Specs)	
		Ref	ClearSky Add-on Kit Options (Dealer Installed):	
	1001237256	Ref	ClearSky Add-on Kit - Canbus (ANSI, ANSI Export & CSA Specs) (Dealer Installed):	
	1001237257	Ref	ClearSky Add-on Kit - Canbus (ANSI Export & CE Specs) (Dealer Installed):	
	1001248502	Ref	ClearSky Add-on Kit - Canbus (Australian Specs) (Dealer Installed):	
	1001248689	Ref	ClearSky Add-on Kit - Access Control (Dealer Installed):	
	1001262959	Ref	Voltage Regulator Location Add-on Kit (Dealer Installaed)	
		Ref	Decal Kit Options:	
	1001239270	Ref	Decal Kit - Master	
	1001234319	Ref	Drive Motor Covers installation	
		Ref	Electrical Connector Kits	
	1001148902	Ref	Amp/Tyco Electrical Connector Kit	
	1001148903	Ref	Deutsch DT Electrical Connector Kit	
	1001148904	Ref	Deutsch HD Electrical Connector Kit	
	1001148905	Ref	Packard Electrical Connector Kit	
	1001148906	Ref	Various Electrical Connector Kit	
	1001245768	Ref	European Subassembly Kit	A
	1001218728	Ref	Fire Extinguisher Installation	
	1001248843	Ref	Foot Latch Add-on Kit (Delaer Installed)	
	1001236547	Ref	Footswitch Installation (Japanese & Korean Specs Only)	
	1001220933	Ref	Height Restricter Switch Installation	
	1001249638	Ref	Inverter Add-on Kit (Dealer Installed)	
	1001250532	Ref	Mobile Control Add-on Kit (Dealer Installed)	
	1001229076	Ref	Noise Reduction Add-on Kit (Dealer Installed)	
	1001229728	Ref	Overhead Protectin Add-on Kit (Dealer Installed)	
	1001239115	Ref	Platform Control Box Cover Add-on Kit (Dealer Installed)	
	1001231309	Ref	Platform Extension Handles Add-on Kit (Dealer Installed)	
	1001262557	Ref	Platform Self Closing Gate Add-on Kit (Dealer Installed)	
	1001262558	Ref	Platform Self Closing Gate Add-on Kit (Dealer Installed)	
	1001234453	Ref	Remote Tow Installation	
	1001224583	Ref	Service Kits List	P
	1001254721	Ref	SkySense Level 1 Add-on Kit (Dealer Installed)	
	1001254542	Ref	SkySense Level 2 Add-on Kit (Dealer Installed)	
	1001255669	Ref	SkySense Level 1 Installation (Factory Installed)	
	1001255883	Ref	SkySense Level 2 Installation (Factory Installed)	
	1001249229	Ref	Strobe (Single) Light Add-on Kit (Dealer Installed)	
	1001249230	Ref	Strobe (Dual) Light Add-on Kit (Dealer Installed)	

MidWestTech | JLG R3246 Scissor Lift Parts Manual | Publication 31215093 Order the manual at mid-west-tech.com >