Illustrated Parts Manual

Model 3246R

P/N
3121752

February 7, 2020 - Rev B

ANSI

CE

AS/NZS

An Oshkosh Corporation Company

MidWestTech | JLG 3246R Scissor Lift Parts Manual | Publication 3121752

Order the manual at mid-west-tech.com >

TABLE OF CONTENTS

SECTION 1 - FRAME 9

FIGURE 1-1. STEER INSTALLATION 10
FIGURE 1-2. DRIVE/BRAKE INSTALLATION 12
FIGURE 1-3. DRIVE MOTOR ASSEMBLY 14
FIGURE 1-4. TIRE/WHEEL INSTALLATION 16
FIGURE 1-5. POTHOLE PROTECTION SYSTEM INSTALLATION 18
FIGURE 1-6. TILT SENSOR INSTALLATION 20
FIGURE 1-7. BATTERY CHARGER INSTALLATION - DELTA-Q (LOCALLY SUPPLIED PLUG) 22
FIGURE 1-8. BATTERY CHARGER INSTALLATION - DELTA-Q (110V PLUG) 24
FIGURE 1-9. BATTERY CHARGER INSTALLATION - DELTA-Q (AUSTRALIAN PLUG) 26
FIGURE 1-10. BATTERY CHARGER INSTALLATION - DELTA-Q (KOREAN PLUG) 28
FIGURE 1-11. BATTERY CHARGER INSTALLATION - EAGLE PERFORMANCE (110V PLUG) 30
FIGURE 1-12. BATTERY CHARGER INSTALLATION - GREEN POWER (LOCALLY SUPPLIED PLUG) 32
FIGURE 1-13. BATTERY CHARGER INSTALLATION - GREEN POWER (CHINA PLUG) 34
FIGURE 1-14. STROBE LIGHT INSTALLATION - SINGLE (AMBER) (WITHOUT GUARD) 36
FIGURE 1-15. STROBE LIGHT INSTALLATION - DUAL (AMBER) (WITHOUT GUARD) 38
FIGURE 1-16. STROBE LIGHT INSTALLATION - SINGLE (AMBER) (WITH GUARD) 40
FIGURE 1-17. STROBE LIGHT INSTALLATION - DUAL (AMBER) (WITH GUARD) 42
FIGURE 1-18. ALARM INSTALLATION (AMBIENT/WHITE NOISE) 44
FIGURE 1-19. LADDER INSTALLATION 46
FIGURE 1-20. FRAME COVERS INSTALLATION 48

SECTION 2 - GROUND CONTROLS 51

FIGURE 2-1. HYDRAULIC COMPONENTS INSTALLATION 52
FIGURE 2-2. MAIN VALVE ASSEMBLY (Prior to SN B20057924, Prior to SN 1200034037) 54
FIGURE 2-3. ELECTRICAL COMPONENTS INSTALLATION (CHINA BUILT MACHINES) 56
FIGURE 2-4. ELECTRICAL COMPONENTS INSTALLATION - #1 (USA BUILT MACHINES) 58
FIGURE 2-5. ELECTRICAL COMPONENTS INSTALLATION - #2 (USA BUILT MACHINES) 60
FIGURE 2-6. MDI INSTALLATION 62
FIGURE 2-7. BATTERIES INSTALLATION - STANDARD 6V-255AH 64
FIGURE 2-8. BATTERIES INSTALLATION - STANDARD 6V-220AH 66
FIGURE 2-9. BATTERIES INSTALLATION - AGM 6V-220AH 68
FIGURE 2-10. BATTERIES INSTALLATION - AGM EVCG 6V-220AH 70
FIGURE 2-11. BATTERIES INSTALLATION - 6V-220AH (TROJAN) 72
FIGURE 2-12. INVERTER INSTALLATION (OPTIONAL) 74
FIGURE 2-13. DOORS INSTALLATION 76

SECTION 3 - SCISSORS ARMS 79

FIGURE 3-1. SCISSORS ARMS INSTALLATION 80
FIGURE 3-2. ARMS GUARD INSTALLATION 84

SECTION 4 - PLATFORM 87

FIGURE 4-1. PLATFORM INSTALLATION 88
FIGURE 4-2. PLATFORM EXTENSION INSTALLATION 90
FIGURE 4-3. RAILS INSTALLATION (SIDE BY SIDE) 92
FIGURE 4-4. RAILS INSTALLATION (TUBE IN TUBE) 94
FIGURE 4-5. EXTENSION HANDLES INSTALLATION (OPTIONAL) 96
FIGURE 4-6. PLATFORM CONSOLE INSTALLATION 98
FIGURE 4-7. CONTROLLER ASSEMBLY 100
FIGURE 4-8. GATE LATCH INSTALLATION 102
FIGURE 4-9. PIPE RACKS INSTALLATION (SIDE BY SIDE RAILS) (OPTIONAL) 104
FIGURE 4-10. PIPE RACKS INSTALLATION (TUBE IN TUBE RAILS) (OPTIONAL) 106
FIGURE 4-11. OVERHEAD PROTECTION INSTALLATION (KOREAN SPECS) 108

SECTION 5 - CYLINDER 111

FIGURE 5-1. LIFT CYLINDER ASSEMBLY 112
FIGURE 5-2. STEER CYLINDER ASSEMBLY 114

SECTION 6 - HYDRAULIC 117

FIGURE 6-1. HYDRAULIC COMPONENTS INSTALLATION 118

MidWestTech | JLG 3246R Scissor Lift Parts Manual | Publication 3121752 Order the manual at mid-west-tech.com >

TABLE OF CONTENTS

SECTION 7 - ELECTRICAL 121

FIGURE 7-1. AC BOX AT PLATFORM INSTALLATION - 110V GFI (ALL SPECS EXCEPT AUSTRALIAN & CE SPECS) 122
FIGURE 7-2. AC BOX AT PLATFORM INSTALLATION - 110V IEC YELLOW (CE SPECS) 124
FIGURE 7-3. AC BOX AT PLATFORM INSTALLATION - 220V IEC BLUE (CE SPECS) 126
FIGURE 7-4. AC BOX AT PLATFORM INSTALLATION - 220V CEE7 POST GROUND (CE SPECS) 128
FIGURE 7-5. AC BOX AT PLATFORM INSTALLATION - 220V CEE7 SIDE GROUND (CE SPECS) 130
FIGURE 7-6. AC BOX AT PLATFORM INSTALLATION - 220V AFSINT 107 (CE SPECS) 132
FIGURE 7-7. AC BOX AT PLATFORM INSTALLATION - 220V CHINA PLUG (CHINA SPECS) 134
FIGURE 7-8. AC BOX AT PLATFORM INSTALLATION - 220V LOCALLY SUPPLIED COMPONENTS (ALL SPECS) 136
FIGURE 7-9. AC BOX AT PLATFORM INSTALLATION - 220V (AUSTRALIAN SPECS) 138
FIGURE 7-10. BREAKER BOX KIT WITH 1 DOUBLE BREAKER 140
FIGURE 7-11. BREAKER BOX KIT WITH 3 BREAKERS 142
FIGURE 7-12. CHASSIS HARNESS 144
FIGURE 7-13. GROUND TO PLATFORM CABLE INSTALLATION - WITHOUT PLATFORM COIL CABLE (CHINA BUILT MACHINES) 148
FIGURE 7-14. GROUND TO PLATFORM CABLE INSTALLATION - WITHOUT PLATFORM COIL CABLE & WITH FOOTSWITCH (CHINA BUILT MACHINES) 150
FIGURE 7-15. GROUND TO PLATFORM CABLE INSTALLATION - WITH PLATFORM COIL CABLE (CHINA BUILT MACHINES) 152
FIGURE 7-16. GROUND TO PLATFORM CABLE INSTALLATION - WITH PLATFORM COIL CABLE & FOOTSWITCH (CHINA BUILT MACHINES) 154
FIGURE 7-17. GROUND TO PLATFORM CABLE INSTALLATION - PLATFORM STRAIGHT CABLE ONLY (USA BUILT MACHINES) 156
FIGURE 7-18. GROUND TO PLATFORM CABLE INSTALLATION - PLATFORM COIL CABLE ONLY (USA BUILT MACHINES) 158
FIGURE 7-19. GROUND TO PLATFORM CABLE INSTALLATION - SCISSORS ARMS CABLE ONLY (USA BUILT MACHINES) 160
FIGURE 7-20. LIFT DOWN HARNESS 162
FIGURE 7-21. PLATFORM CONTROL BOX HARNESS 164
FIGURE 7-22. RECEPTACLE BOX KIT - 110V GFI 166
FIGURE 7-23. RECEPTACLE BOX KIT - 110V IEC YELLOW 168
FIGURE 7-24. RECEPTACLE BOX KIT - 220V IEC BLUE 170
FIGURE 7-25. RECEPTACLE BOX KIT - 220V CEE7 POST GROUND 2X4 BOX (CE SPEC) 172
FIGURE 7-26. RECEPTACLE BOX KIT - 220V CEE7 SIDE GROUND 174
FIGURE 7-27. RECEPTACLE BOX KIT - 220V AFSINT 107 (CE SPEC) 176

SECTION 8 - DECALS 179

FIGURE 8-1. DECAL INSTALLATION (ANSI SPECS) 180
FIGURE 8-2. DECAL INSTALLATION (AUSTRALIAN SPECS) 182
FIGURE 8-3. DECAL INSTALLATION (BRAZIL SPECS) 184
FIGURE 8-4. DECAL INSTALLATION (CE SPECS) 186
FIGURE 8-5. DECAL INSTALLATION (CHINA SPECS) 188
FIGURE 8-6. DECAL INSTALLATION (CSA SPECS) 190
FIGURE 8-7. DECAL INSTALLATION (KOREAN SPECS) 192
FIGURE 8-8. DECAL INSTALLATION (LATIN AMERICAN SPECS) 194
FIGURE 8-9. DECAL INSTALLATION - OPTIONS 196

SECTION 9 - RECOMMENDED SERVICE PARTS STOCK 199

FIGURE 9-1. RECOMMENDED SERVICE PARTS STOCK 200

SECTION 10 - SPECIAL OPTIONS 201

FIGURE 10-1. SPECIAL OPTIONS 202

PART NUMBER INDEX 203

MidWestTech | JLG 3246R Scissor Lift Parts Manual | Publication 3121752 Order the manual at mid-west-tech.com >

FIGURE 5-1. LIFT CYLINDER ASSEMBLY

ITEM	PART NUMBER	QTY	DESCRIPTION	REV
	1001244417	Ref	LIFT CYLINDER ASSEMBLY	C
1	See Note:	NSS	Barrel (Note: Purchase Complete Part)	
2	70007050	1	Rod	
3	70007051	1	Head	
4	See Note	NSS	Wiper (Note: Use Item 50)	
5	70050795	1	Ring, Retaining	
6	See Note	NSS	Seal, Rod (Note: Use Item 50)	
7	See Note	NSS	Ring, Back-up (Note: Use Item 50)	
8	70007052	1	Bearing	
9	See Note	NSS	O-Ring (Note: Use Item 50)	
10	See Note	NSS	Ring, Back-up (Note: Use Item 50)	
11	See Note	NSS	O-Ring (Note: Use Item 50)	
12	70007053	1	Piston	
13	See Note	NSS	Seal, Piston (Note: Use Item 50)	
14	See Note	NSS	Ring, Wear (Note: Use Item 50)	
15	See Note	NSS	O-Ring (Note: Use Item 50)	
16	70007054	2	Fitting	
17	2220883	4	Plug	
18	0961948	4	Bearing	
19	70007055	1	Orifice	
20	70004585	1	Cartridge, Valve	
21	70005236	1	Cartridge, Solenoid Valve	
22	70022564	1	Ball	
23	70023369	1	Setscrew	
50	70007056	1	Seal Kit - 1001244417 Cylinder (Includes Items 4, 6, 7, 9-11 & 13-15)	

MidWestTech | JLG 3246R Scissor Lift Parts Manual | Publication 3121752 Order the manual at mid-west-tech.com >

FIGURE 7-16. GROUND TO PLATFORM CABLE INSTALLATION - WITH PLATFORM COIL CABLE & FOOTSWITCH (CHINA BUILT MACHINES)

ITEM	PART NUMBER	QTY	DESCRIPTION	REV
	1001234096	Ref	GROUND TO PLATFORM CABLE INSTALLATION - WITH PLATFORM COIL CABLE AND FOOTSWITCH	A
1	4240017	AR	Tie-Strap (Not Shown)	
2	1001223262	1	Platform Harness	
2	4460899	1	Receptacle, Female - 6 Position (To Item 3)	
2	4460464	4	Pin, Male	
2	4460943	2	Pin, Male	
2	4460754	1	Connector - 14 Position (To Console Box)	
2	4460465	8	Socket, Female	
2	4460944	2	Socket, Female	
2	4460466	4	Plug, Terminal	
2	4460891	1	Plug, Male - 2 Position (To Footswitch)	
2	4460465	2	Socket, Female	
2	4460897	1	Receptacle, Female - 2 Position (Footswitch Jumper)	
2	4460464	2	Pin, Male	
2	4460539	1	Plug, Male - 3 Position (To Overhead Switches)	
2	4460465	2	Socket, Female	
2	4460466	1	Plug, Terminal	
3	1001234631	1	Cable Assembly - Ground to Platform	
3	4460894	1	Plug, Male - 6 Position (To Platform Harness Item 2)	
3	4460465	4	Socket, Female	
3	4460944	2	Socket, Female	
3	4460899	1	Receptacle, Female - 6 Position (To Chassis Harness)	
3	4460464	4	Pin, Male	
3	4460943	2	Pin, Male	

MidWestTech | JLG 3246R Scissor Lift Parts Manual | Publication 3121752 Order the manual at mid-west-tech.com >

FIGURE 8-9. DECAL INSTALLATION - OPTIONS

ITEM	PART NUMBER	QTY	DESCRIPTION	REV
		Ref	DECAL INSTALLATION - OPTIONS:	
25	1001217894	Ref	Corner Stripes Installation	
25	4420051	62 in/ 156 cm	Tape, Safety	
30		Ref	Decal - Capacity Options:	
30	1001237115	1	Decal - Capacity (705LB/320KG)	
30	1001245409	Ref	Decal - Capacity (with Dual Languages)	
30	1001237115	1	Decal - Capacity (705LB/320KG)	
30	1001216865	1	Plate, Decal Mounting	
44	1706312	4	Decal - Maximum Tire Load	
71	See Note	NSS	Decal - Manufacturers Serial Number (Note: Not Available for Purchase)	
110	1001214779	Ref	JLG Decals Installation	
110A	1703177	2	Decal - JLG	
110B	1705754	1	Decal - JLG	
110C	1705781	2	Decal - JLG	
156	1001173703	1	Decal - EAC (Russian/CIS Specs)	

MidWestTech | JLG 3246R Scissor Lift Parts Manual | Publication 3121752 Order the manual at mid-west-tech.com >